

CITY OF TROUTDALE
CONSTRUCTION DETAILS
INTERIM CHANGES

TABLE OF CONTENTS

IC 1 – Sanitary Sewer Manhole Locations, Spacing, Inverts.....	tab 1
IC 2 – Number of Water Service Meters per Property	tab 2
IC 3 – RECINDED	tab 3
IC 4 – Add New Drawing II-29 – Town Center Overlay Street .	tab 4
IC 5 – RECINDED	tab 5
IC 6 – Gravel Construction Entrance Rock.....	tab 6
IC 7 – Superseded by IC #'s 39 and 27	tab 7
IC 8 – Access Management for Driveways.....	tab 8
IC 9 – Superseded by IC #10.....	tab 9
IC 10 – Superseded by IC #19.....	tab 10
IC 11 – Catch Basins Filter Bags, Biobags	tab 11
IC 12 – Fire Hydrants	tab 12
IC 13 – Certification of Buildable Lots.....	tab 13
IC 14 – Meter Makes/Models Deleted.....	tab 14
IC 15 – Storm Sewer Design	tab 15
IC 16 – Storm Sewer Collection – Rainfall Intensities.....	tab 16
IC 17 – Drawing II-1 Updated - C/I Street Cross Section	tab 17
IC 18 – Drawing VIII-3 Replaced - Manhole Base	tab 18
IC 19 – Superseded by IC #30.....	tab 19
IC 20 – Fire Hydrant Drawings Replaced.....	tab 20
IC 21 – Vertical Datum and As-Built Survey Requirements....	tab 21
IC 22 – OHA-DWP Plan Review Exemption – Water Mains...	tab 22
IC 23 – ODEQ Exemption – Gravity Sanitary Sewer	tab 23
IC 24 – Sidewalk Ramp Drawings Replaced	tab 24
IC 25 – Stormwater Quality Treatment (PSWMM).....	tab 25
IC 26 – Rescinded see IC #39	tab 26
IC 27 – Acceptable Water Meter Boxes.....	tab 27
IC 28 – Clustered Mailboxes	tab 28
IC 29 – Sidewalk Cutting/Grinding	tab 29
IC 30 – Driveway Drawings Replaced, Driveway Locations	tab 30
IC 31 – Drawing Replaced – 14' Wide Speed Hump	tab 31

IC 32 - Meter Box Specifications for ¾ & 1" Service Laterals....	tab 32
IC 33 - Driveway & Sidewalk Concrete & Rock Standards.....	tab 33
IC 34 - Erosion Control Standards.....	tab 34
IC 35 - Stormwater Quality Treatment Requirements.....	tab 35
IC 36 - Sidewalk Ramps.....	tab 36
IC 37 - Garbage and Recycling.....	tab 37
IC 38 - Hydrants and blow-offs at dead-end water mains.....	tab 38
IC 39 - Water Meters.....	tab 39
IC 40 - Replacement of American Public Works Assoc. Standards.....	tab 40

CITY OF TROUTDALE CONSTRUCTION DETAILS

TABLE OF CONTENTS

PART I - STREETS

Streets (General Requirements)	I - 1
Standards for Pavement Overlays	I - 4

PART II - STREETS (Construction Details)

Commercial/Industrial Street (cross section)	II - 1
Neighborhood Collector (cross section)	II - 2
Local Street (cross section)	II - 3
Cul-de-sac & Intersection Radii	II - 4
Curbs & Weepholes	II - 5
Straight Curb	II - 6
Curb Knock-out for Driveways	II - 7
Concrete Cross Gutters	II - 8
Wheel Chair Ramps	II - 9
Concrete Sidewalk	II - 10
Driveway Approach (Single Family Residential)	II - 11
Driveway Approach (Multi-Family Residential, Commercial/Industrial)	II - 12
Utility Easement Access Way	II - 13
Street Cut & Repairs	II - 14
Street Light Pole Location (back of walk)	II - 15
Street Light Pole Location (in landscaping strip)	II - 16
Mail Box Installations (cluster & single)	II - 17
Survey Monument & Box	II - 18
Street Barricade (Type II)	II - 19
Street Barricade (Types I & III)	II - 20
Public/Private Utility Locations	II - 21
Bomanite Pedestrian Crosswalk	II - 22
Neighborhood Watch Signs	II - 23

Private Street Sign.....	II - 24
14' Wide Speed Hump	II - 25
Gravel Construction Entrance	II - 26
Not a Permanent Dead-End Street Sign	II - 27
In-Concrete Sidewalk Street Sign Sleeve Detail.....	II - 28

PART III - WATER DISTRIBUTION SYSTEM

Water Distribution System (General Requirements).....	III - 1
---	---------

PART IV - WATER DISTRIBUTION SYSTEM (Construction Details)

Thrust Blocks	IV - 1
Fire Hydrant Assembly (Behind Sidewalk).....	IV - 2
Fire Hydrant Assembly (Behind Curb).....	IV - 3
Valve Box & Operator Extension Assembly	IV - 4
Air Release Valve Assembly	IV - 5
Air & Vacuum Release Valve Assembly	IV - 6
Water Sampling Station	IV - 7
1" Double Water Service.....	IV - 8
3/4" to 2" Single Water Service.....	IV - 9
In Cul-de-sac Double/Single Service Configuration.....	IV - 10
In Half Cul-de-sac Double/Single Service Configuration.....	IV - 11
3" Diameter (and larger) Water Meter Vault.....	IV - 12
Meter with Remote Reader & Vault.....	IV - 13
Water Meter with Bypass Detail.....	IV - 14
Pressure Regulating Vault	IV - 15
Double Check Backflow Preventor Device Vault	IV - 16
Dead-end Blowoff Assembly	IV - 17
In-line Blowoff Assembly	IV - 18

PART V - STORM SEWER COLLECTION SYSTEM

Storm Sewer Collection System (General Requirements)	V - 1
---	-------

PART VI - STORM SEWER COLLECTION SYSTEM
(Construction Details)

Catch Basin	VI - 1
Ditch Inlet.....	VI - 2
Flat Area Inlet (Unimproved Surfaces Only).....	VI - 3
Flat Top Manhole (Storm Only)	VI - 4
Large Concrete Storm Manhole Bases.....	VI - 5
Drywell Detail	VI - 6
Storm Sewer Lateral & Marker (Shallow Trench)	VI - 7
Storm Sewer Lateral (Deep Trench)	VI - 8
Storm Manhole (48" Diameter)	VI - 9
Permitted Drywell Construction Area	VI - 10

PART VII - SANITARY SEWER COLLECTION SYSTEM

Sanitary Sewer Collection System (General Requirements)	VII - 1
--	---------

PART VIII - SANITARY SEWER COLLECTION SYSTEM
(Construction Details)

Sanitary Manhole (48" Diameter)	VIII - 1
Manhole Lids & Frames (Sanitary & Storm)	VIII - 2
48" Manhole Base (Sanitary or Storm).....	VIII - 3
Trench Backfill, Bedding & Pipe Zone	VIII - 4
Inside Drop Connection for Manholes (San. or Storm).....	VIII - 5
Outside Drop Connection for Manholes (San. or Storm).....	VIII - 6
Cleanout.....	VIII - 7
Sanitary & Storm Manholes & Cleanouts Marker Post	VIII - 8
Sanitary Sewer Lateral & Marker (Shallow Trench).....	VIII - 9
Sanitary Sewer Lateral (Deep Trench)	VIII - 10
Manhole Ring Adjustments (Sanitary & Storm).....	VIII - 11
Cam-Lock Manhole Cover & Frame (Cast Iron & Aluminum).....	VIII - 12
Bore Casing Detail.....	VIII - 13
Concrete Cradle & Cap Detail	VIII - 14

Pipe Anchor Detail	VIII - 15
Concrete Apron Detail.....	VIII - 16

PART IX - EROSION CONTROL MEASURES

Erosion Control Measures (General Requirements)	IX - 1
--	--------

PART X - EROSION CONTROL MEASURES

(Construction Details)

Temporary Sediment Fence.....	X - 1
Temporary Straw Bale Silt Barrier	X - 2
Biofilter Bags in Ditches & Swales.....	X - 3
Biofilter Bag for Overland Water Flow (Option 1)	X - 4
Biofilter Bag for Overland Water Flow (Option 2)	X - 5
Biofilter Bag - Protected Catch Basin Detail	X - 6
Temporary Site Interceptor (Swales & Dikes).....	X - 7
Erosion Control for Single Lots	X - 8
Filter Bag Inlet Detail	X - 9
Sediment Trap	X - 10
Sediment Pond	X - 11
Erosion Control Blanket Installation Detail	X - 12
Continuous Geosynthetic Berm.....	X - 13

PART XI - GARBAGE & RECYCLING CONTAINER ENCLOSURES

Garbage & Recycling Container Enclosures (General Requirements)	XI - 1
--	--------

PART XII - GARBAGE & RECYCLING CONTAINER ENCLOSURES

Garbage & Recycling Container Enclosures (Construction Details)

Multi-Family Sample 1	XII - 1
Multi-Family Sample 2	XII - 2

Multi-Family Sample 3.....	XII - 3
Commercial Sample 1.....	XII - 4
Commercial Sample 2.....	XII - 5
Commercial Sample 3.....	XII - 6
Commercial Sample 4.....	XII - 7
Commercial Sample 5.....	XII - 8
Commercial Sample 6.....	XII - 9

